## FLORIDA SOLAR ENERGY CENTER

1679 CLEARLAKE ROAD, COCOA, FLORIDA 32922-5703 (321) 638-1000



## **Approved Solar Energy System**

FSEC # S9099 Approval Date: SEP 1995

Revision Date: JAN 2004

DISTRIBUTOR

1. None

SYSTEM

Thermal Conversion Technology 101 Copeland Street Jacksonville, Florida 32204 ProgressivTube PT-30-CN (2)

This system was evaluated by the Florida Solar Energy Center (FSEC) in accordance with the Florida Standards Program For Solar Domestic Water and Pool Heating Systems (FSEC-GP-7-80) and was found to meet the minimum standards established by FSEC.

North

South/Central

The calculated Florida Energy Factors for this system are:

9.8


Greater than 15

**Description** 

Collector Manufacturer	Model Number	Units	Total Rating (Btu)
1. Thermal Conversion Tech.	PT-30-CN	2	44,200*
* NET based on FSEC Solar Rating valid only for units	r System Test plumbed in parallel		
Tank Manufacturer	Model Number	Capacity (gal)	Type: Direct
1. Integral Storage		60.8	
Pump Manufacturer	Model Number	Power Draw (W	atts) Rated Power
1. None			
Controller Manufacturer	Model Number	Type:	
1. None			
Freeze Protection			
Thermal mass     Manual draining			
2. Manual draining			
Other Major Components			

If further information is required you may contact the Florida Solar Energy Center at the above address.


## SYSTEM PLUMBING DIAGRAMS PRE-HEATER SOLAR SYSTEMS




2-WAY SYSTEM FOR ELECTRIC WATER HEATERS 2-WAY SYSTEM
FOR GAS WATER HEATERS

## Two Unit System Piped in Parallel

The collectors in two unit systems <u>MUST</u> be piped in parallel as shown in either of these drawings



Caution: pipe between units must be of equal length between inlet and outlet fittings.



This unit is flippped over so the outlet becomes the inlet and the inlet becomes the outlet.